

PLAN 4

PLANNING APPLICATION PLN-20-0287

SHEEPWASH CREEK BETWEEN PHILLIP AND EDWARD STS, PROPERTIES BORDERING PHILLIP STREET, YOUL ROAD & EDWARD STREET, PERTH

ATTACHMENTS

- A Application & plans
- B Responses from referral agencies
- C Representations & Response from Hydrodynamica

PLANNING APPLICATION
Proposal

Description of proposal: CREEK WIDENING AND RE-ALIGNMENT
WORKS AND REMOVAL OF VEGETATION

(attach additional sheets if necessary)

If applying for a subdivision which creates a new road, please supply three proposed names for the road, in order of preference:

1..... 2..... 3.....

Site address: SHEEPWASH CRK, BETWEEN PHILLIP + EDWARD ST'S,
REXTH

CT no: See attached


Estimated cost of project \$60,000..... (include cost of landscaping, car parks etc for commercial/industrial uses)


Are there any existing buildings on this property? Yes / (No)
If yes - main building is used as

If variation to Planning Scheme provisions requested, justification to be provided:
.....
.....
.....
.....

(attach additional sheets if necessary)


Is any signage required? NO
(if yes, provide details)

Owner: <i>Maxwell Harry Bird and Ruth Dogmar Bird.</i>	PLAN OF SURVEY by Surveyor... <i>P. Richmond.</i> of land situated in the	Registered Number: S.P 32733
Title Reference: <i>C.T. 3258-55.</i>	TOWN OF PERTH.	Approved Effective from: <i>1 FEB. 1988.</i>
Grantee: <i>Whole of 8^a 1^o 28^a Section W. 9th. to Edmund Arntica.</i>	SCALE 1:1500. MEASUREMENTS IN METRES	




EXHIBITED

OWNER GRAEME JOHN SEMMENS JULIE ANNE SEMMENS PETER LEONARD DENNIS	PLAN OF SURVEY BY SURVEYOR R.M.Peck	REGISTERED NUMBER P179011
FOLIO REFERENCE C.T.32733/1 C.T.236039/1	LOCATION TOWN OF PERTH Section W	APPROVED 18 SEP 2020 EFFECTIVE FROM <i>[Signature]</i>
MAPSHEET MUNICIPAL CODE No 123 (5039)	LAST UPI No	LAST PLAN No. P236039, SP32733
GRANTEE Part of 8°1'29", Section W, Granted to Edmund Anstice Part of 6°1'18" Granted to Joseph Clayton		ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN







EXHIBITED

<p>PLAN OF SURVEY ANNEXURE SHEET SHEET 1 OF 2 SHEETS</p>	<p>OWNER: See Sheet 1 FOLIO REFERENCE: See Sheet 1 SCALE 1:750 LENGTH IN METRES</p>	<p>Registered Number P 179011</p>
<p>SIGNED FOR IDENTIFICATION PURPOSES <i>[Signature]</i> <u>16/3/2020</u> Council Delegate Date</p>	<p>THIS ANNEXURE SHEET FORMS PART OF THE ATTACHED INDEX PLAN. THE SURVEYORS CERTIFICATE EXTENDS TO THE DETAILS ON THIS SHEET <i>[Signature]</i> <u>10/3/20</u> Registered Land Surveyor Date</p>	<p>APPROVED EFFECTIVE FROM <u>18 SEP 2020</u> <i>[Signature]</i> Recorder of Titles</p>




EXHIBITED


<p>PLAN OF SURVEY ANNEXURE SHEET SHEET 2 OF 2 SHEETS</p>	<p>OWNER: See Sheet 1 FOLIO REFERENCE: See Sheet 1 SCALE 1:750 LENGTH IN METRES</p>	<p>Registered Number P 1790 11</p>
<p>SIGNED FOR IDENTIFICATION PURPOSES  Council Delegate 16-3-2020 Date</p>	<p>THIS ANNEXURE SHEET FORMS PART OF THE ATTACHED INDEX PLAN. THE SURVEYORS CERTIFICATE EXTENDS TO THE DETAILS ON THIS SHEET  Registered Land Surveyor 16/3/20 Date</p>	<p>APPROVED EFFECTIVE FROM 18 SEP 2020  Recorder of Titles</p>




EXHIBITED




EXHIBITED




EXHIBITED

OWNER PETER FREDERICK WATTS MERLE SUZANNE WATTS KENNETH ANDREW WRIGHT ANDREW PETER CHUGG SUZANNE MARY CHUGG FOLIO REFERENCE C.T.32733/3, C.T.32733/4 C.T.155124/2	PLAN OF SURVEY BY SURVEYOR R.M.Peck LOCATION TOWN OF PERTH Section W SCALE 1:1500 LENGTHS IN METRES		REGISTERED NUMBER SP178888
	6ty° 19.137		APPROVED EFFECTIVE FROM - 6 NOV 2020  Recorder of Titles



MAPSHEET MUNICIPAL CODE No 123 (5039)	LAST UPI No	LAST PLAN No. SP155124, SP32733	ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN
---------------------------------------	-------------	---------------------------------	---




EXHIBITED




EXHIBITED


PLAN OF SURVEY ANNEXURE SHEET SHEET 2 OF 2 SHEETS	OWNER: See Sheet 1 FOLIO REFERENCE: See Sheet 1 SCALE 1:750 LENGTH IN METRES	Registered Number SP.1788888
	SIGNED FOR IDENTIFICATION PURPOSES  16/3/2020 Council Delegate Date	THIS ANNEXURE SHEET FORMS PART OF THE ATTACHED INDEX PLAN. THE SURVEYOR'S CERTIFICATE EXTENDS TO THE DETAILS ON THIS SHEET  19/3/20 Registered Land Surveyor Date




EXHIBITED





EXHIBITED




EXHIBITED




EXHIBITED

OWNER PETER FREDERICK WATTS MERLE SUZANNE WATTS KENNETH ANDREW WRIGHT ANDREW PETER CHUGG SUZANNE MARY CHUGG FOLIO REFERENCE C.T.32733/3, C.T.32733/4 C.T.155124/2	PLAN OF SURVEY BY SURVEYOR R.M. Peck LOCATION TOWN OF PERTH Section W SCALE 1:1500 LENGTHS IN METRES		REGISTERED NUMBER SP178888
			APPROVED EFFECTIVE FROM - 6 NOV 2020  Recorder of Titles




MAPSHEET MUNICIPAL CODE No 123 (5039)	LAST UPI No	LAST PLAN No. SP155124, SP32733	ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN
---------------------------------------	-------------	---------------------------------	---




EXHIBITED




EXHIBITED

PLAN OF SURVEY ANNEXURE SHEET SHEET 2 OF 2 SHEETS	OWNER: See Sheet 1	Registered Number
	FOLIO REFERENCE: See Sheet 1	SP.178888
SIGNED FOR IDENTIFICATION PURPOSES	SCALE 1:750	LENGTH IN METRES
 Council Delegate	 Registered Land Surveyor	APPROVED EFFECTIVE FROM - 6 NOV 2020  Recorder of Titles
16-3-2020 Date	19/3/20 Date	



EXHIBITED

OWNER : MICHAEL RONALD GADSBY & ANNETTE CHRISTINA GADSBY		PLAN OF SURVEY BY SURVEYOR MARTIN RALPH HEATLEY of PDA SURVEYORS 3/23 BRISBANE STREET, LAUNCESTON		REGISTERED NUMBER SP168369	
FOLIO REFERENCE : C.T. 32733/5				LOCATION TOWN OF PERTH (SECTION W)	
GRANTEE : WHOLE OF 8A - 1R - 29Ps, G1d. TO EDMUND ANSTICE		SCALE: 1:500	LENGTHS IN METRES	SURVEYORS REF: 138/14	
MAPSHEET MUNICIPAL CODE No. 123 (5039)	LAST UPI No	LAST PLAN No. (SP32733)		ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN	




[Signature]
COUNCIL DELEGATE
DATE 2 10-14


EXHIBITED

OWNER GRAEME JOHN SEMMENS JULIE ANNE SEMMENS PETER LEONARD DENNIS	PLAN OF SURVEY BY SURVEYOR R.M.Peck	REGISTERED NUMBER P179011
FOLIO REFERENCE C.T.32733/1 C.T.236039/1	LOCATION TOWN OF PERTH Section W	APPROVED 18 SEP 2020 EFFECTIVE FROM <i>[Signature]</i> Recorder of Titles
	SCALE 1:1500 LENGTHS IN METRES	

MAPSHEET MUNICIPAL CODE No 123 (5039)	LAST UPI No	LAST PLAN No. P236039, SP32733	ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN
---------------------------------------	-------------	--------------------------------	---




EXHIBITED




EXHIBITED




EXHIBITED

OWNER SHERVAN DEVELOPMENTS PTY. LTD.	PLAN OF SURVEY		REGISTERED NUMBER SP164089
FOLIO REFERENCE C.T.5392-1	BY SURVEYOR R.V.TAIT		APPROVED EFFECTIVE FROM 16 JUL 2012 <i>Alice Kawa</i> Recorder of Titles
GRANTEE PART OF 6 ^A 1 ^R 8 ^P (LOTS 8,9,10,11,12 & 13) GRANTED TO JOSEPH CLAYTON.	LOCATION TOWN OF PERTH SECTION W		
MAPSHEET MUNICIPAL CODE No 123 (5039-24)	LAST UPI No 5601112	LAST PLAN No. S.P.5392	ALL EXISTING SURVEY NUMBERS TO BE CROSS REFERENCED ON THIS PLAN



11.204

 12-7-2012
COUNCIL DELEGATE DATE

EXHIBITED

SHEEPWASH CREEK PROPOSED DRAIN WIDENING AND REALIGNMENT WORKS

Scale 1:1000



1-187



NOTES

- Vegetation to be removed marked in red
- Drain dimensions are approximate only and may vary based on existing ground levels on site.

DRAIN TYPICAL CROSS SECTION



EXHIBITED

Rosemary Jones

From: Jonathan Galbraith
Sent: Monday, 7 December 2020 12:35 PM
To: NMC Planning
Cc: Leigh McCullagh
Subject: Sheepwash creek vegetation removal

Rosemary,

As discussed I confirm that we will save as many trees as possible when the drain upgrade works are carried out. The plan shows the areas where trees may have to be removed but when works are carried out we will be able to make a decision based on site conditions which trees can be saved. We also intend to plant a larger number of trees than what will be removed.

Our Longford office is open from 8:45am until 4:30pm weekdays, however meetings with Council Officers are by appointment only, and we ask that transactions be conducted via telephone or online wherever possible. Our Customer Service team can be contacted by phone, post, via our website or email at council@nmc.tas.gov.au
Our priority is to keep our community, including staff, ratepayers and residents safe and to minimise the spread of COVID-19.

Regards,

Jonathan Galbraith



Engineering Officer | Northern Midlands Council
Council Office, 13 Smith Street (PO Box 156), Longford Tasmania 7301
T: (03) 6397 7303 | M: 0400 935 642 | F: (03) 6397 7331
E: jonathan.galbraith@nmc.tas.gov.au | W: www.northernmidlands.tas.gov.au

Tasmania's Historic Heart

**employer
of choice**

EXHIBITED

SOIL MANAGEMENT AND INSTREAM WORKS PLAN – SHEEPWASH CREEK, PERTH

Council propose to carry out widening and re-alignment works on Sheepwash Creek between Edward and Phillips Streets in Perth.

It is proposed to widen and re-align the creek and remove weeds to reduce the risk of flooding and erosion. The works will allow the area to be easily accessed for ongoing maintenance. Works will be carried out within and beside the existing creek and there is unlikely to be any significant disturbance to land either side of the creek which might require sediment fences or other measures to prevent sediment entering the water.

Works will be carried out in accordance with Wetlands and Waterways Works Manual, Best Practice 2003. The following sections (attached) are particularly relevant to this work;

- 2 – Construction of Wetlands
- 3 – Excavation in Waterways

EXHIBITED

Environmental Best Practice Guidelines 2.

Construction Practices in Waterways and Wetlands

Undertaking works in waterways and wetlands without expert advice can cause environmental harm that may be difficult and expensive to remediate.

1. Potential environmental effects

Undertaking works and operating machinery in and near waterways and wetlands can cause environmental harm by

- eroding stream beds and banks
- filling in deep holes and pools
- destroying riparian and wetland vegetation
- smothering aquatic vegetation
- killing aquatic animals
- polluting water
- exacerbating flooding.

2. Environmental management principles

Before starting works in waterways and wetlands a works plan should be prepared. The plan should outline the works to be undertaken and the measures that will be used to minimise the risk of causing environmental harm. The measures outlined should include those described below. These measures should be required of all contractors and plant operators working in waterways and wetlands.

2.1 Prepare for works

- Expert advice should be sought before excavating in waterways and wetlands. Depending on the scale of the works, advice may needed from one or more experts, including a stream biologist, river engineer, fluvial geomorphologist or hydrologist.
- The risk of causing environmental harm should be minimised. Short-term disturbances may be unavoidable but steps should be taken to minimise their effects at the site as well as upstream and downstream of the site. The environmental harm that could result from the works should be assessed and measures developed to minimise the harm. For example, works should be avoided when aquatic species are migrating and birds are breeding.
- The proposed construction methods and procedures should be specified in the works plan.
- All downstream neighbours and river users, such as water authorities, should be notified of the works.
- All relevant authorisations for the works should be obtained. See *Environmental Best Practice Guidelines 1. Legislative and Policy Requirements for Protecting Waterways and Wetlands when Undertaking Works*.
- Everyone involved in the works should attend a site briefing before starting work.

2.2 Minimise sediment disturbance and control erosion

- The works should be scheduled appropriately. For example, works should be timed to coincide with periods of low flow and completed quickly, and works should be stopped if conditions are not suitable, such as during and after heavy rain.
- Damage to the ground cover should be minimised and confined to the works site. Blading and grubbing of the banks and the area adjacent to the works site should be avoided. The width of

any access tracks should be minimised. Vegetation on unstable and erodible banks should be cleared by hand. If possible, trees should be felled away from the waterway.

- In-stream structures (culverts, etc) should be installed according to the manufacturer's specifications.
- The type and size of any heavy machinery and attachments (eg crab-grab) should be appropriate for the site and the works being done.
- All machinery should be kept out of the waterway on dry and stable areas within the works site.
- Existing crossings should be used to move equipment across the waterway. If there is no crossing and the stream must be crossed, any disturbance should be minimised. If crossing once, the machinery should be carefully 'walked' across the stream. If crossing many times, a temporary crossing should be made by laying a pad of clean rock at a shallow point of the waterway. The rock should be removed when works have finished.



Keep machinery off wet and unstable areas

- When excavating the channel, the flow should be diverted and the works site isolated. Sometimes, if the environmental risk is small and the flow is low, it may be possible to do the works without a diversion structure. The stream should be diverted by constructing a cofferdam, berm or temporary channel. The cofferdam should be constructed using sandbags, clean rock, steel sheeting or other non-erodible material. Clean rock is rock of varying type and size, that contains no fines, soil, wastes and contaminants. Temporary diversion channels should be protected by lining them with non-erodible materials to the high water mark.



If excavating the channel isolate the works site

- Boulders, rock, shingle, gravels, soil and vegetation from the stream bed and banks should not be used or removed without authorisation. Any use or removal should be specified by a river engineer.
- Excavated material should be placed well away from the waterway to minimise erosion back into the stream. Fill should not be pushed into the waterway or stored in flood-prone areas.
- Surface and sub-surface flows at the site should be managed to minimise erosion and sedimentation of the waterway or wetland. Geo-textile sediment fences should be used to stop sediment entering the water. They should be installed along the bases of fills and cuts, on the downhill side of soil stockpiles, and along stream banks and around wetlands adjacent to cleared areas. They should be installed along a contour, and be entrenched and staked. They should extend the full width of the cleared area.
- Any runoff from the works site should be diverted into a settling pond or sediment trap, or through a vegetated area to stop sediment entering the waterway or wetland. The settling basin or sediment trap should be designed so its capacity is large enough for the size of the area being drained and the volume of water being treated.
- The publications listed in 'Section 3. References' contain detailed information on managing soil and water at works sites.



Sediment fences need maintenance to remain effective

2.3 Avoid contaminant spills

- All workers should be trained and equipped to contain equipment spills and leaks.
- If a spill occurs, immediate steps should be taken to stop it polluting the water, including the ground water. The spill should be reported to the appropriate authorities as soon as possible.
- Petroleum products and other hazardous substances should be kept out of the waterway. Refuelling, top-ups and oil checks should be done well away from the waterway. Fuel, and servicing and refuelling equipment should be stored so the fluids cannot enter the waterway.

Non-toxic hydraulic fluids, such as vegetable-based fluids, should be used if possible. All equipment should be inspected and repaired regularly to prevent oil and other fluids leaking into the waterway.

- If equipment is to be immersed in the waterway, it should be cleaned beforehand to remove any external grease, oil and other fluids. Wash-down water is not to enter the stream.
- Dirt and mud should be removed from all equipment before entering the works site and waterway to avoid transferring weeds and disease. Wash-down water is not to enter the stream.
- Fresh concrete should be kept out of the waterway. If practical, prefabricated structures and precast components should be transported to the site and assembled on site. Any cast-in-place concrete should be isolated from the waterway for at least 48 hours to allow the pH to neutralise.
- Paints should not be allowed to enter the waterway when constructing, repairing and maintaining in-stream structures.
- When using wood treated with preservatives, the chemicals should be given enough time to fix before immersing the wood in the water.

2.4 Stabilise and rehabilitate banks

- The site should be rehabilitated when the works have finished. If practical, native vegetation should be established on all exposed soil surfaces, including the headslopes of any bridges and culverts.
- Temporary erosion control measures, such as geo-textile silt fences, diversion ditches, sediment traps and temporary seeding with fast growing annuals, should be used to control erosion at the works site and in the table drains of any approach roads. These should remain in place until the long-term erosion control methods are established and functioning.
- Long-term measures should be used to control erosion at the works site. Suitable measures include slope stabilisation, revegetation, soil coverings, rip-rap and armouring, check dams, sediment traps, brush barriers and vegetation filters. The measures used should be inspected and maintained regularly to make sure they are effective.

3. References

- Hobart Regional Councils. 1999. *Guidelines for Soil and Water Management*. Hobart Regional Councils, Hobart.
- Hobart Regional Councils. 1999. *The Soil and Water Management Code of Practice for Hobart Regional Councils*. Hobart Regional Councils, Hobart.
- Launceston City Council. 2000. *The Soil and Water Management Code of Practice for Launceston City Council*. Launceston City Council, Launceston.

These guidelines should be used in conjunction with the appropriate technical advice and literature.

Disclaimer: Any representation, statement, opinion or advice, expressed or implied in this publication is made in good faith but on the basis that the Department of Primary Industries, Water and Environment, its agents and employees are not liable (whether by reason of negligence, lack of care or otherwise) to any person for any damage or loss whatsoever which has occurred or may occur in relation to that person taking or not taking (as the case may be) action in respect of any representation or advice referred to herein.

Checklist

This checklist summarises the environmental management principles outlined in *Environmental Best Practice Guidelines 2. Construction Practices in Waterways and Wetlands*. The plan of works prepared should describe the proposed works and show that the measures listed below will be used to minimise the risk of causing environmental harm during and after the works.

- Works plan prepared

Prepare for works (Section 2.1)

- Expert advice sought
- Risk of causing environmental harm assessed
- Construction methods and procedures specified
- Downstream neighbours notified
- Water authorities notified if appropriate
- Appropriate authorisations obtained
- All site workers briefed

Minimise sediment disturbance and control erosion (Section 2.2)

- Works scheduled appropriately
- Ground cover disturbance minimised
- In-stream structures installed to manufacturer's specifications
- Heavy equipment appropriate for site and works
- Machinery restricted to dry and stable areas
- Crossing sites selected if appropriate
- Works site isolated from channel
- Any removal of boulders, rock, shingle, gravels, soil and vegetation authorised
- Excavated material placed away from waterway
- Sediment control devices selected and sited appropriately

Avoid contaminant spills (Section 2.3)

- Contingency plan prepared that outlines measures to minimise likelihood of spills on site and response if spills occur
- Workers trained and equipped to contain spills
- Refuelling and servicing equipment located away from waterway
- Arrangements made to clean vehicles and other equipment away from waterway
- Hazardous materials kept out of waterway

Stabilise and rehabilitate banks (Section 2.4)

- Site rehabilitated and stabilised
- Temporary erosion control measures installed
- Long-term erosion control measures installed and inspection and maintenance plan prepared

Environmental Best Practice Guidelines 3.

Excavating in Waterways

Many works in waterways involve excavating stream beds and banks. Such works include stabilising stream beds, protecting and stabilising stream banks, diverting streams, creating channels to drain land and alleviate floods, deepening stream holes to increase the capacity of water off-takes, extracting sand and gravel, and works associated with developing infrastructure, such as bridges and pipelines.

Excavating can severely degrade or destroy ecosystems in waterways and wetlands so the precautionary principle should be followed. Excavating should not be allowed if it is likely to cause significant environmental harm. If the works will result in substantial benefits and minimal harm to the waterway and surrounding environment, excavating the bed and banks may be acceptable. However, the appropriate safeguards must be taken.

1. Potential environmental effects

1.1 Changes stream geomorphology

River systems will move towards a state of dynamic equilibrium after disturbance. A stream modified by removing alluvial material or channelising will attempt to revert to its 'natural' state. The resulting erosion, increased sediment transport, and reduced water quality may continue or even accelerate for many years after the works have been completed. Continual maintenance may be needed to control this process.

Removing alluvial material from the stream bed

Extracting material from the stream bed can trigger changes in the stream profile, along the stream and from bank to bank. Changes to the flow regime and disturbing the balance between the supply of sediment and the sediment carrying capacity of the flow can have the following effects.

Headcut erodes the stream bed: Excavating the channel deepens the stream bed. A nick point is created in the bed at the point where the flow velocities increase due to the steeper gradient. If the increased flow velocities erode the stream bed, the nick point migrates upstream in a process known as 'headcutting'. This continues until the gradient of the stream stabilises or the nick point meets an obstacle, such as a rock outcrop. Headcutting releases large amounts of sediment from the stream bed, which is transported and deposited downstream. The deposition fills in deep holes and pools, and changes the form of the channel.



Headcut eroding stream bed

Increased flow capacity affects sediment movement: Excavating the channel increases its cross-sectional area and hence its flow capacity. Larger floods ('1 in 2 year floods' and up) are more readily contained within the modified channel and are less likely to have their energy dissipated across the flood plain. This increases the stream energy during floods, which further erodes the channel, and increases sediment supply and transport from the stream reach.

Collapse of stream banks due to increased height: Deepening the stream bed can increase the height of the stream banks and make them more prone to erosion and collapse. If the banks collapse, the sediment load in the stream will increase. Widening of the stream due to extensive bank collapse increases flow capacity, and increases sediment supply and transport downstream.

Removal of gravel armouring the stream bed: Removing gravel that is protecting or 'armouring' the stream bed and stabilising the banks and bars may expose material that is more susceptible to erosion. If this occurs, excessive scouring of the bed and movement of sediment may result.

Loss of stream roughness: Removing objects that create roughness in the stream, such as large woody debris and boulders, when excavating can reduce the structural integrity of the stream and ecosystem health. These objects help control the morphology and hydraulics of the stream, and help regulate the storage of gravel and other sediments.


Channelising

In general, increasing the stream's flood carrying capacity by channelising the stream - that is, re-aligning the channel and smoothing the banks - decreases the stability of the stream. This can result in unforeseen and unintended erosion upstream and downstream of the channelled section.


Increased slope increases flow velocities: Constructing meander cut-off channels and re-aligning the stream usually shortens the stream, which steepens its gradient. Abrupt changes in the slope of the channel cause erosion and degradation of the channel upstream, and aggradation (increased silt, sand or gravel deposition) of the channel downstream (see Figure).

The significance of increased flow velocities depends on the composition of the bed and banks and the state of the riparian vegetation cover. Coarse, rough materials, such as cobbles and gravel, are more resistant to erosion from increased flow velocities than clay, fine sand and unconsolidated fill. A wide, healthy cover of native riparian vegetation helps resist erosion.


Increased flow downstream increases bank erosion: Larger volumes of flow being funnelled downstream can destabilise the banks due to the greater erosive forces of the flow and more frequent overtopping of the banks. The amount of water flowing in a waterway shapes the profile of the stream channel (along with sediment load) so increasing the flow may trigger further changes in the stream profile.



Channel diversion & loss of meander will shorten the channel, and...



...this will increase the slope of stream bed, which...



... increases flow velocity, causing 'headcut' erosion in the upstream direction and sediment deposition downstream.

Bed erosion due to channel diversion
(adapted from W.A. Water & Rivers Commission,
River Restoration Report No. RR10 - Stream Stabilisation.)

1.2 Effects on surface and ground water flows

In-stream works can change the local hydrology and lead to unpredictable changes in the surface and ground water flows.

Removing alluvial material

Excavating the stream bed and banks may lead to

- a lower water table
- reduced bank storage
- drainage of associated wetlands
- greater variations in stream flow
- more intermittent stream flows
- more uniform stream flow conditions.

Channelising

Straightening the stream and smoothing the banks will increase the flow capacity and flow velocities of the stream. This may have a number of consequences, including

- The higher average flow velocities may aggravate flooding downstream.
- The greater quantity of water flowing may trigger unintended changes in the course of the stream.
- Improved drainage of the land adjacent to the stream may increase the discharge of ground water, which may reduce the amount of water available for stream flows during dry periods.
- Stockpiles of soil and overburden left on the floodplain after excavating may change the hydraulics of the channel during floods.

1.3 Degrades aquatic and riparian habitat

The physical and biological changes arising from works in streams may reduce the abundance, composition and diversity of plant and animal species, especially sensitive species, and reduce the health of ecosystems. The effects may not be confined to the works site. They may also extend a long way upstream and downstream.

Excessive suspended sediment: Excavating changes the physical composition and stability of substrates in the stream and releases large amounts of sediment into the stream. Other activities at the works site, such as clearing, grading, stockpiling of materials and constructing an access track, can erode soil into the waterway and increase sediment loads (see *Environmental Best Practice Guidelines 2. Construction Practices in Waterways and Wetlands*). Clearing the riparian vegetation when excavating may increase the sediment load in the stream because less sediment is filtered from the overland flow. Operating heavy equipment in the channel bed can increase turbidity and suspended sediment downstream (see *Environmental Best Practice Guidelines 2. Construction Practices in Waterways and Wetlands*).

Increased sediment loads and increased deposition can create an unstable environment that is hostile to many fish and other aquatic animals by

- creating conditions favourable only to silt-tolerant plants and animals
- reducing the availability of benthic food due to smothering
- reducing light penetration and productivity of the waterway
- making it difficult for plants and animals to respire
- reducing the tolerance of fish to diseases and pollutants
- increasing physiological stress in fish by clogging and damaging their gills
- smothering fish eggs and reducing the success of spawning.

Removal of riparian vegetation: Trees and vegetation may have to be removed from the banks so workers and equipment can reach the excavation site. Collapse of the stream banks and lowering of the water table as a result of excavation works can also destroy riparian vegetation. Less riparian vegetation may

- exacerbate fluctuations in water temperature and reduce the concentration of oxygen in the water by reducing shade
- reduce the amount of food, shelter, and spawning and breeding habitat available for aquatic and terrestrial animals.



Channelising the stream can destroy riparian habitat


Less diversity of aquatic habitat: Channelising the stream produces a straight, uniform channel with fewer features, such as pools, riffles, and undercut banks, that are important habitat for aquatic animals. Removing large woody debris, boulders, and so on during excavation works further simplifies the structure of the stream and reduces the range of habitats available. Operating heavy equipment in the channel bed may degrade or destroy habitat.

Habitat may also be lost if the works result in a shallower stream. Low water levels may expose riffles and cobble substrate in high gradient streams, and logs and snags in low gradient streams - all of which are important habitat for fish and other aquatic animals.

Restricts fish movement: Shallower surface flows caused by excavating in the stream may stop fish migrating upstream during low flows. The water may be too shallow for fish to remain submerged as they cross shallow sections. Previously submerged structures, such as logs and rock shelves, may no longer be submerged and may create a barrier that fish cannot get over.

1.4 Damages infrastructure

Erosion triggered by excavating the stream may damage public and private property far from the works site. Channel incision may undermine bridge piers and expose buried pipelines and utility lines. Exacerbating flooding downstream may increase the risk of damaging infrastructure and necessitate the construction of flood-protection structures, such as flood levees.



Excavating the stream may lead to infrastructure loss

Excavating streams does not always cause instability upstream and downstream. However, nearby landowners may attribute such problems to the excavation works and may take legal action to recoup their perceived costs.

1.5 Degrades water quality

Excavating streams can increase sediment loads and turbidity downstream, which may degrade the quality of domestic and stock water supplies. A new channel course may increase or decrease runoff and sediment input from the adjacent land. If the increased runoff is from agricultural land, more salts, nutrients and pesticides may be discharged into the stream. If town water supplies have to be treated, this will involve additional costs for the supplier.

1.6 Reduces recreational and aesthetic values

Recreational activities, such as fishing, swimming and bird-watching, need streams that are relatively free of sediment and visible pollutants. Excavating streams can reduce their recreational values if sediments and pollutants are mobilised. Preserving landforms and vegetation cover when excavating will preserve the stream's aesthetic values.

2. Methods for controlling erosion

Before undertaking works to control erosion in streams it must be determined that the rate of erosion justifies the cost of the works, and that the works are likely to be successful and not create new problems. The methods used will depend on the scale of the erosion problem. Methods that stabilise and protect the banks are usually appropriate for managing localised bank instability, such as erosion of meander bends. If there is severe degradation of the stream bed, the bed may need to be stabilised before stabilising the banks. A variety of bed-control structures (also referred to as grade-control or full-width structures) can be used for this purpose. Extensive degradation of the river system may need a catchment-based approach that focuses on changing land use in the catchment.

The design requirements of structures to control and stabilise stream beds and banks can be found in the following publications

- The WES Stream Investigation and Streambank Stabilization Handbook (Biedenharn et al., 1997)
- Riparian Land Management Technical Guidelines Volume 2: On-ground Management Tools and Techniques (Lovett & Price, 2002)
- A Rehabilitation Manual for Australian Streams, Volume 2 (Rutherford et al., 2000)
- Guidelines for Stabilising Waterways (SCR&C, 1991)
- Stream Stabilisation. River Restoration Report No. 10 (WRC, 2001b).

2.1 Stabilising the banks

The two main approaches to controlling bank instability are re-aligning the flow and modifying the stream bank. At some sites both approaches will be needed.

Re-aligning the flow

The re-aligning approach uses structures that extend part-way into the channel to redirect the flow so the hydraulic forces along the bank are reduced and do not cause erosion, or the flow is directed away from the erodible bank. The partial-width structures most commonly used are groyne (extend

from the eroding bend into the channel at an angle to the flow) and retards (a series of piles with cross members that provide a permeable barrier to flow). Large woody debris anchored to the bank can also be used (see *Environmental Best Practice Guidelines 6. Managing Large Woody Debris in Waterways*). If placed appropriately, a series of any of these structures will reduce flow velocities near the bank and increase sediment deposition along the bank, which will allow revegetation.



Seek expert advice if installing bank stabilisation structures such as pin groynes


Other structures that can be used are pin retards (unconnected pins), brush retards (pins connected by branches), jacks (tripods anchored by cables to each other and the bed), and low flow deflectors (low profile structures extending into the stream).

Modifying the banks

Stream flow is not the only cause of bank erosion. Inadequate vegetation cover, trampling by stock, and overland flow can also trigger bank erosion. It is important to determine the cause of the erosion so the most appropriate remedy can be used. The range of remedies is considerable. Revegetating the bank is probably the best remedy from an environmental and aesthetic perspective. However, revegetation must be combined with other approaches if the bank instability is too great. Battering or terracing the bank may be necessary to reduce the slope of the bank and allow plants to establish. Using organic geo-textile mats (natural fibre mats) will provide better conditions for growing plants if the area is not subject to high velocity flows. If the bank instability is due to undermining of the bank, the bank toe can be hardened by installing rock gabions (stone-filled wire cages) or rock rip-rap (loose rock). Dead trees and root wads can be used instead of rock in some situations.

2.2 Stabilising the bed

Bed-control structures stabilise the stream bed. They stop the active headcut moving upstream (including into tributaries) by creating a hard point in the bed that resists the erosive forces. Alternatively, they change the hydraulic conditions so the stream energy no longer scours the bed. Some bed-control structures do both.



Seek expert advice if installing bed control structures such as rock chutes

Bed-control structures usually span the width of the channel and allow some overflow. They also allow a temporary backwater pool to form upstream, and a permanent, stable scour pool to form downstream. Rock chutes are the most commonly used bed-control structures because rock is long lasting and copes with high flows. Grass chutes are sometimes used on seasonal waterways with low base flows. Reinforced-concrete drop structures and piped drops are less desirable because they may stop fish swimming upstream. Timber, can also be used, either a single log that spans the channel to form a low weir or angled logs that meet in the centre and concentrate low flows.

2.3 Changing land use in the catchment

Activities such as clearing vegetation, draining wetlands and damming streams will affect erosion in the catchment's waterways by changing the sediment loads and water yields. A catchment-based approach, such as a natural resource management framework, can be used to restore the sediment loads and water yields in the catchment to as close to their 'natural' levels as possible. For example, sediment going into the catchment's waterways may be reduced by establishing riparian buffer zones throughout the catchment and promoting better ways of managing stormwater.

3. Environmental management principles

Before excavating in waterways and wetlands a works plan should be prepared. The plan should outline the works to be undertaken and the measures that will be used to minimise the risk of causing environmental harm. The measures outlined should include those described below.

3.1 Get expert advice

- Undertaking works in streams without expert advice can cause environmental harm that may be difficult and expensive to remediate. Expert advice should be sought before excavating the bed and banks of waterways. Depending on the scale of the works, advice may be needed from one or more experts, including a stream biologist, river engineer, fluvial geomorphologist or hydrologist.

3.2 Avoid works on high risk sites

- The location and extent of any proposed excavation should be assessed on a case-by-case basis.
- The proposed works should meet the requirements of all relevant legislation, policies and regional strategies. Other ways of achieving the objectives of the works should be considered.
- Streams containing threatened plants and animals and having pristine ecosystem Protected Environmental Values should not be excavated.
- Significant geomorphological and cultural heritage sites should be protected.
- Avoid excavating upstream of nearby drinking water supplies and industrial water off-takes that need high quality water.
- The risk of damaging public and private infrastructure should be considered.
- The works should not damage recreational and aesthetic amenities.
- The likelihood that the sediments contain toxic materials, such as pesticides and metals, should be determined. If sediments upstream and downstream of the works site could be disturbed, these should also be assessed.
- Extracting sand and gravel from a waterway is only acceptable in rare situations where it benefits the waterway and surrounding environment. For example, where human activities outside the river reach have caused a build-up of sand and gravel (sediment slugs) that has eroded or changed the course of the stream, or destroyed habitat.

3.3 Understand site and system

- Waterways are complex systems and excavating them can cause unexpected consequences. Having accurate information about the stream channel and the discharge of water that shapes it, is critical to ensuring the works will be successful and harm minimised. Information about the geomorphology and land use in the catchment and sub-catchment should also be obtained. Stream Channel Analysis. River Restoration Report No. 9 (WRC, 2001a) (available on the internet) describes the information that should be collected before starting works. Groups and individuals excavating streams without this information risk causing environmental degradation, and having structures fail and costly maintenance problems afterwards.

Desk top survey	Field work	Calculations
to gather information about the stream area and catchment history	to survey the stream and its catchment and gather information from locals	based on the information gathered that help plan the works
Catchment area and use	Longitudinal channel survey	Channel slope
Estimates of channel dimensions	Bank-full level	Average bank-full
Flow records	Stream cross-section	Wetted perimeter
Determine channel forming flow from flow records	Existing flow velocity	Channel roughness
Longitudinal survey of river channel	Assess bed material	Hydraulic radius
	Sketch map of channel	Median bed paving
	Assess foreshore and habitat	Flow velocity
		Discharge
		Stream power
		Critical flow

3.4 Adopt construction practices guidelines

- Contractors and plant operators undertaking works in streams should adopt the principles outlined in *Environmental Best Practice Guidelines 2. Construction Practices in Waterways and Wetlands* to minimise the risk of causing environmental harm. These guidelines focus on preparing for works, controlling sediment and erosion, avoiding contaminant spills, and stabilising and rehabilitating the stream.

3.5 Retain stream geometry, materials and habitat

- The stream should be restored to its 'natural' state after works have been completed. This will be easier if information about the waterway's environmental and aesthetic values was collected before the works started. Similar healthy, unmodified reaches in the catchment can be used as models if the site is degraded.
- Local, natural materials, such as rock and timber, should be used if possible. Artificial materials, such as concrete, old tyres and gabions, are less attractive. They also create a different flow regime to that of the original channel, need considerable maintenance, and do not provide good habitat for aquatic animals. The local materials should come from an appropriate source, such as an approved quarry.
- Creating large discontinuities in the water surface profile should be avoided. A vertical drop of more than 10 centimetres will stop native fish swimming upstream.
- A series of structures (eg a pool and riffle sequence or a series of large woody debris) should be used rather than a single structure if possible. More complex structures create a greater variety of habitats while still preventing erosion.
- Elements that create roughness in the stream, such as large woody debris, are critical for maintaining healthy aquatic ecosystems and should be restored.

3.6 Stabilise stream diversion (if required)

- If the channel is being re-aligned, the flow must be diverted into a properly designed and constructed channel that has been stabilised. It should not be diverted into an undefined channel.

3.7 Protect stream-entry points

- If extensive surface runoff may enter the receiving channel, the runoff should be directed through properly designed and constructed drainage ditches.
- It is best if drainage ditches and streams have small gradients as they approach and enter the receiving channel. If the gradient of the incoming drain or stream is steep, it may be necessary to line it with protective rock to prevent erosion of the receiving stream. If necessary, rip-rap may be used to line the bank of the receiving channel and prevent erosion and slumping of its banks.

3.8 Avoid constructing levee banks

- Levee banks are considered to be channel works even though they are not constructed in the stream channel. Levee banks deepen the flow channel during floods, which increases the likelihood of erosion along the stream bed and banks.
- Using large, long levees to prevent flooding of flood plains adversely affects the channel system and adjacent areas. Wetlands and riparian areas often rely on flooding to supply nutrients and trigger plant growth. Diverting flood waters away from these areas may make it difficult or impossible for plants to survive.
- If possible, development should be avoided on flood-prone areas. This removes the need to construct flood-protection structures.

3.9 Revegetate

- Deep-rooted plants, such as trees and shrubs, should be planted along the banks to stabilise the channel, provide shade to control water temperature, provide habitat and food for animals, and create an attractive and healthy waterway. Local, native riparian species should be used if possible.

- The works site should be monitored and maintained after revegetation to make sure the plants establish and weeds are controlled.

4. References

- Biedenharn, D., Elliott, C. & Watson, C. 1997. *The WES Stream Investigation and Streambank Stabilization Handbook*. US Army Engineer, Mississippi.
<http://chl.wes.army.mil/library/publications/>
- Department of Primary Industries, Water & Environment. 1999. *Quarry Code of Practice*. DPIWE, Hobart. <http://www.dier.tas.gov.au>
- Goulburn Broken Catchment Authority. 2000. *Works on Waterways Notes No. 4. Sand and Gravel Extractions*. GBCA, Shepparton. <http://www.gbcma.vic.gov.au/publicationsframe.html>
- Lovett, S. & Price, P. (eds). 2002. *Riparian Land Management Technical Guidelines Volume 2: On-ground Management Tools and Techniques*. Land & Water Australia, Canberra.
<http://www.rivers.gov.au/publicat/guidelines.htm>
- Rutherford, I., Jerie, K. & Marsh, N. 2000. *A Rehabilitation Manual for Australian Streams, Volumes 1 and 2*. Land & Water Resources Research & Development Corporation, Canberra.
<http://www.rivers.gov.au/publicat.htm>
- Standing Committee on Rivers & Catchments. 1991. *Guidelines for Stabilising Waterways*. Rural Water Commission of Victoria, Victoria.
- Water & Rivers Commission. 2001a. *Stream Channel Analysis. River Restoration Report No. 9*. WRC, Perth. <http://www.wrc.wa.gov.au/public/RiverRestoration/index.htm>
- Water & Rivers Commission. 2001b. *Stream Stabilisation. River Restoration Report No. 10*. WRC, Perth. <http://www.wrc.wa.gov.au/public/RiverRestoration/index.htm>

These guidelines should be used in conjunction with the appropriate technical advice and literature.

Disclaimer: Any representation, statement, opinion or advice, expressed or implied in this publication is made in good faith but on the basis that the Department of Primary Industries, Water and Environment, its agents and employees are not liable (whether by reason of negligence, lack of care or otherwise) to any person for any damage or loss whatsoever which has occurred or may occur in relation to that person taking or not taking (as the case may be) action in respect of any representation or advice referred to herein.

Checklist

This checklist summarises the environmental management principles outlined in *Environmental Best Practice Guidelines 3. Excavating in Waterways*. The plan of works prepared for all works involving excavation in a waterway should describe the proposed works and show that the measures listed below will be used to minimise the risk of causing environmental harm during and after the works.

- Works plan prepared

Methods for controlling erosion (Section 2)

- Appropriate erosion-control method/s selected

Get expert advice (Section 3.1)

- Expert advice sought

Avoid works on high risk sites (Section 3.2)

- Environmental risk assessed
- Legislative and policy requirements met
- Sensitive ecosystems protected
- Geomorphological and cultural heritage sites protected
- Downstream water supplies and sensitive industrial off-takes not affected
- Public and private infrastructure not threatened
- Recreational and aesthetic effects minimal
- Public safety and use protected
- Contaminated sediments not present

Understand site and system (Section 3.3)

- Stream survey undertaken

Adopt construction practices guidelines (Section 3.4)

- Works conform to *Environmental Best Practice Guidelines 2. Construction Practices in Waterways and Wetlands*

Retain stream geometry, materials and habitat (Section 3.5)

- Natural geometry, materials and habitat maintained or restored

Stabilise stream diversion (Section 3.6)

- Diversion channels stabilised

Protect stream-entry points (Section 3.7)

- Stream entry points protected

Avoid constructing levee banks (Section 3.8)

- Flood protection used to minimise environmental effects

Revegetate (Section 3.9)

- Rehabilitation and revegetation program prepared

REFERRAL OF DEVELOPMENT APPLICATION PLN-20-0287 TO WORKS & INFRASTRUCTURE DEPARTMENT

Property/Subdivision No: 108500.0

Date: 9 December 2020

Applicant: Northern Midlands Council

Proposal: Creek widening, realignment works & vegetation removal

Location: Sheepwash Creek between Phillip and Edward Sts, Properties bordering Phillip Street, Youl Road & Edward Street, Perth

W&I referral PLN-20-0287, Sheepwash Creek between Phillip and Edward Sts, Properties bordering Phillip Street, Youl Road & Edward Street, Perth

Planning admin: W&I fees paid.

No W&I comment

Jonathan Galbraith (Engineering Officer)

Date: 9/12/20

15 December 2020

Planning Department
Northern Midlands Council
13 Smith St
Longford TASMANIA 7301

Planning Application Reference: PLN-20-0287

Site: Sheepwash Creek between Phillip and Edward Streets

Representation to this proposal:

- 1) Please provide the name of the Proponent, and if the NMC who is the responsible person.
- 2) The Application contains no working drawings or engineering reports.
- 3) The Application contains no flooding, stormwater, water quality control or anything associated with such. The increased speed, flow and quality of water is of a significant impact given the bottle neck at Drummond St. In a recent application, we had to provide all of the above and have it re-certified at the request of the council despite having no impact on the water systems. The Council would need to clearly demonstrate this information per any other applicant.
- 4) Given the proponent is likely the NMC, the estimate of \$60k should be fully itemised and provided as part of the report given cost overruns previously on Council projects.

Regards and Thanks

Andrew McCullagh

Karen Jenkins

From: Peter Dennis <peterdennis06@gmail.com>
Sent: Sunday, 20 December 2020 8:43 PM
To: NMC Planning
Subject: Sheepwash Creek

Follow Up Flag: Follow up
Flag Status: Flagged

Dear Mr. Jennings,

I am writing to ask you how can you do this work on Sheepwash Creek when you haven't paid for the land yet.

I feel that your workers will be trespassing on my property .

There shouldn't be any work down till the property is settled.

Also why are so many trees being taken out when it is supposed to to be parkland .

Your's Sincerely Peter Dennis.

Erin Miles

From: Cameron Oakley <ckoakley75@outlook.com> on behalf of Cameron Oakley <Cameron.Oakley@h-dna.com.au>
Sent: Friday, 18 December 2020 2:50 PM
To: Jonathan Galbraith
Cc: Erin Miles
Subject: RE: Representation to Sheepwash Crk tree removal and creek widening

Follow Up Flag: Follow up
Flag Status: Flagged

Hi guys, if you can provide a couple of the application/extent of work shown that would be handy.

Re point 2) in the representor's email below.

Are working drawings required? We have the Sheepwash Creek Proposed Improvements v01 drawing which shows the overall proposed works/improvements. I assume the application just covers some of the creek widening works? Council have an obligation and right to undertake works as the Drainage Authority on its own stormwater system. The Sheepwash Creek flood study report(s) detail the amount of work that has gone into our assessment of the site in order to understand the flood risks. However, it is not a specific report for this application.

Re 3) below. Again, is there any requirement in the Scheme to provide such information Erin?

I'm not sure what the application contained, however the purpose of the widening is to alleviate flooding. We have flood maps which show how the overall works, of which this work is a part, will benefit the township. These can be supplied by Council required; assuming they are not available for general release. Increase in speed will initially be nominal, as these works do not include any culvert upgrade works. As such flows will remain constrained at road and rail crossings, as will therefore the velocity of peak flooding. Velocity is generally relatively low as the topography is so flat and there will be negligible affect on the Drummond Street.

Obviously water within the creek-line is a hazard, however it can be better managed there within the stormwater system than if when spills out.

In the Water Quality Code we may need to address A1/P1 (soil & water management plan) if native vegetation is being removed, I seem to recall some backwoods. Also, is there anything with the creek which is identified as a wetland? If not I can't see anything else that is application. Most of the code seems to relate to subdivisions.

Happy to touch base on this next week if required.

Regards,

Cameron Oakley
Hydrodynamica
0431208450
cameron.oakley@h-dna.com.au
